

Order Number

Serial Number

PRODUCT/TEST MANUAL

2C58K17

INSTANTANEOUS OVERCURRENT RELAY

Issue Level	Date	Summary of changes
C	12/03/1999	Initial issue.

Due to RMS continuous product improvement policy this information is subject to change without notice.

Document updated	Checked	Registered	.pdf file created	.pdf uploaded to web site

1. BROAD DESCRIPTION

The 2C58K17 is a triple-pole single output instantaneous overcurrent relay having less than 20ms operate and 15ms release times at 20X setting current. Heavy duty output contacts capable of breaking 0.5A at 110V DC resistive are provided. Air-cored current transformers are used to enable fast operate times to be maintained regardless of previous current offsets which may have occurred.

2. SPECIFICATIONS

Auxiliary Supply Voltage	125V DC	+10% -30%
Auxiliary Supply Burden (at 125V)	<3W output relay dropped out <11W output relay picked up	
Nominal Input Current	1A	
Sensing Supply Burden (at 1A)	<0.1VA	
Nominal Setting Range	20% - 80% continuously variable per pole	
Number of Poles	3 (with common output)	
Frequency Tolerance	-6% to +2% of 50Hz	
Ambient Temperature Range	-5°C to 55°C	
Accuracy	<±5% of maximum setting	
Dropout/Pickup Ratio	70% Nominal	
Withstand Current (independent of setting)	5A continuous 20A for 3 seconds	
Operate Time	<20ms Symmetrical or fully offset	
Release Time	<15ms Symmetrical or fully offset with current interruption at a zero current crossing	

2. SPECIFICATIONS (Cont)

Output Relay Contact Ratings

Make and Carry Continuously

3000 VA AC resistive with maximums of 660 Volt and 12 Amp
3000 VA DC resistive with maximums of 660 Volt and 12 Amp

Make and Carry of 0.5 Second

7500 VA AC resistive with maximums of 660 Volt and 30 Amp
7500 VA DC resistive with maximums of 660 Volt and 30 amp

AC Break Capacity

3000 VA AC resistive with maximums of 660 Volt and 12 Amp

DC Break Capacity (Amps)

Voltage			24V	48V	125V	250V
Resistive rating		a	12	1.5	0.5	0.25
		b	12	12	10	5
L/R=40mS	Maximum break	a	12	1	0.4	0.2
		b	30	15	5.5	3.5
	1K operations (N3 Rating)	b	12	12	5	2.5

a = Without magnetic blowouts b = With magnetic blowouts

* As tested by Powernet Yarraville laboratories in Victoria.

3. TEST EQUIPMENT REQUIRED

DC Auxiliary Supply
AC Current Supply
AC Ammeter
Electronic Timer
Decade Box
Oscilloscope
High Voltage Test Equipment.

4. ASSOCIATED DRAWINGS

159-058-117 Wiring Diagram
660-093-204 PCB circuit diagram
660-093-301 PCB Loading

5. HIGH VOLTAGE TESTING

- a) Apply 2KV RMS. between the terminal groups as listed in A & B below for 1 minute.
- b) Apply three 5KV 1/50usec pulses of each polarity as listed in A & B below.

GROUP A

7,8,10,11,12,13,16,17,18,22
10,11,12,13,25,26,43,44
7,8,10,11,16,17,25,26,40,41
7,8

GROUP B

25,26,40,41,43,44,E
7,8,16,17,18,22,40,41,e
12,13,18,22,43,44,e
16,17,E

6. CALIBRATION PROCEDURE

6.1 Current Sensing

Note:

The calibration of only one phase of the circuit will be described (Input No. A). Component reference numbers refer to 660.093.204.

- a) Adjust pot knob for equal overtravel at scale ends if necessary.
- b) Apply scale minimum current through input A (terminals 25 & 26).
- c) Connect a decade box across R1 (159.058.145 reference) avlugs located on mother board 660/94-404. The value of R1 determines the value of pickup current at a particular dial setting.
- d) Apply auxiliary supply voltage of 125V DC.
- e) Check that TP"E" waveform is clean, and varies by a factor of four to one in amplitude as the dial pot is moved from min to max setting. R3 may be decreased if the scale span is too small or increased if the scale span is too large.
- f) Check that TP"F" waveform is as smooth as possible (ie symmetrical 3 phase ripple). If percentage ripple is too great, C5 may be altered to achieve best symmetry.
- g) Adjust decade box so that relay just picks up at 0.8A for dial setting of 0.8A.
- h) Check that at the 0.2A dial setting, pickup occurs at this value.

6.1 Current Sensing (Cont)

- i) Replace decade box with nearest preference value of fixed resistor, and check the following scale calibration points.

MINIMUM	MAXIMUM	NOMINAL	ACTUAL	UNIT
170	230	200	<input type="text"/>	mA
370	430	400	<input type="text"/>	mA
570	630	600	<input type="text"/>	mA
770	830	800	<input type="text"/>	mA

- j) Check that hysteresis is between 67% and 74%. Repeat (f) if not.

Actual %

- k) Repeat steps (a)-(i) for input B :
 Ref (b) Terminals 43 & 44 (c) R2
 (e) TP'C' R21 (f) TP'D' C15

MINIMUM	MAXIMUM	NOMINAL	ACTUAL	UNIT
170	230	200	<input type="text"/>	mA
370	430	400	<input type="text"/>	mA
570	630	600	<input type="text"/>	mA
770	830	800	<input type="text"/>	mA

- l) Check that hysteresis is between 67% and 74%. Repeat (f) if not.

Actual %

- m) Repeat steps (a)-(i) for input C :
 Ref (b) Terminals 40 & 41 (c) R3
 (e) TP'A' R39 (f) TP'B', C25

MINIMUM	MAXIMUM	NOMINAL	ACTUAL	UNIT
170	230	200	<input type="text"/>	mA
370	430	400	<input type="text"/>	mA
570	630	600	<input type="text"/>	mA
770	830	800	<input type="text"/>	mA

- n) Check that hysteresis is between 67% and 74%. Repeat (f) if not.

Actual %

6.2 OPERATE TIME CHECK

- a) Set input A dial to 0.2A and input A current to 4A.

PU time <19ms @ aux supply 87.5V	
DO time <14ms @ aux supply 137.5V	

- b) Set input B dial to 0.2A and input A current to 4A.

PU time <19ms @ aux supply 87.5V	
DO time <14ms @ aux supply 137.5V	

- c) Set input C dial to 0.2A and input A current to 4A.

PU time <19ms @ aux supply 87.5V	
DO time <14ms @ aux supply 137.5V	

7. GENERAL & FUNCTIONAL

- a) Check that unit operates satisfactorily over the range of 87.5% to 137.5% auxiliary supply.
- b) Check that R7 and R8 have been correctly loaded on mother board.
- c) Check that quiescent current at 125V is <40ma +10% with output relay dropped out and <140mA with output relay picked up.
- d) Check that the relay is electrically sound and mechanically robust as per Standard Inspection & Test Schedule 903-000-026

PASS

TESTED BY : _____ DATE : _____

8. CONNECTION DIAGRAM

