

## PRODUCT / TEST MANUAL

# 2C83K1

### OVERCURRENT & EARTH FAULT RELAY



Order Number

RMS Serial Number

Vaasa Serial Number

Issue	Date	Summary of changes
A	10/10/00	Initial issue.

Due to RMS continuous product improvement policy this information is subject to change without notice.  
 This document is uncontrolled and subject to copyright.

Author	Checked & Registered	.pdf file created	Released
ERL	MW	MW	

## 1. BROAD DESCRIPTION

The 2C83 overcurrent & earth fault relay is a non directional current measuring protection relay incorporating both definite and inverse time characteristics. The relay can be programmed either by using the front panel display or by connecting a PC to the front panel programming port.

## 2. SPECIFICATIONS

**STATUS INPUT** 48 Volts DC +/- 10%

### ACCURACY

Overcurrent Stage +/- 2% of setting  
Residual Current stage +/- 2% of set value or 0.3% of rated value.

**AUXILIARY SUPPLY** 40 - 275 V DC Switchmode power supply

**RESET TIME** Electronic reset time is between 20 and 50 millisecond.  
Output relay dropout time is less than 20 millisecond and removal of auxiliary supply will reset the relay in this time.

**INSULATION WITHSTAND** In accordance with, IEC 60255-5:2KV RMS between input and frame, output and frame, and output and input. 1.2/50 5KV impulse between each terminal and earth, between circuits not normally connected together and between terminals of the same circuit.

**NOISE IMMUNITY** Withstands the high frequency interference test detailed in IEC 60255-5.

**OUTPUT CONTACTS** The relay is fitted with 5 N/O + 1 N/C contacts as standard.

### OUTPUT RELAY CONTACT RATINGS

#### Trip contacts (2N/O)

Rated Voltage 250V AC or DC  
Carry continuously 5A  
Make 2000W /VA  
Break 50W DC L/R=40ms

#### Alarm contacts (3 N/O + 1 N/C)

Rated voltage 250V AC or DC  
Carry continuously 5A  
Make 2000W /VA

**COMMUNICATION** RS232

**3. TEST EQUIPMENT REQUIRED**

DC Auxiliary Supply, Digital Voltmeter, Oscilloscope, High Voltage Test Equipment , Current source

**4. ASSOCIATED DRAWINGS**

159-083-101 Wiring Diagram  
VPJ140 factory test report  
VPJ140 factory insulation report

**5. HIGH VOLTAGE TESTING**

- a) Apply 2KV RMS 50 Hz between terminal groups 1 and 2 in Table 1 for 1 minute.
- b) Apply 3 pulses of each polarity of 5 Kv 1/50 between terminal groups 1 & 2 in Table 1

<u>Group 1</u>	<u>Group 2</u>
55,56,5,7,29,30,35,36,41,42	47,48,49,50,9 to 23,26,28,25,27 + E
55,56,5,7,47,48,49,50	29,30,35,36,41,42,26,28,25,27 + E
55,56,29,30,41,42,49,50,26,28 + E	5,7,35,36,47,48,9 to 23,25,27
29,30,47,48,26,28,25,27	41,42,9 to 23 + E

Table 1

**6. FUNCTIONAL CHECKS**

- 6.1 Apply nominal volts to the DC input, ensure the display on the front panel powers up and reports "setting".
- 6.2 Ensure the relay "Power on" LED is lit and there are no errors reported by the error LED.
- 6.3 Operate the front panel menu navigation buttons ensuring that the buttons perform the correct directional control.
- 6.4 Check that the relay operates at the correct level (refer to factory calibration sheet)
- 6.5 Repeat this test for all other current inputs, select appropriate current magnitude as per the factory sheet to suit the relative inputs ie current stage, earth fault stage
- 6.6 Connect PC to RS232 port and ensure correct operation, (Use Vepset software). Download Test1.vps to unit under test.

**6. FUNCTIONAL CHECKS (Cont)**

6.7 Check all output relay contacts.

A1	I>	2.5 Amp	250A	500/5	Contacts 21 - 23
T1	I>	2.5 Amp	5.0 secs		Contacts 26 - 28
A2	Io>	0.05 Amp	5A	100/1	Contacts 17 - 19
T2	Io>	0.05Amp	1.0 secs		Contacts 25 - 27
A3	Digital Input		48 VDC		Contacts 13 - 15
	P/S fail alarm				Contacts 9 - 11

6.8 Check analogue output with terminal 3 being positive.

6.9 Check that the relay is electrically sound and mechanically robust as per Standard Inspection & Test Schedule 903.000.026.

6.10 Check that the completed Vaasa test & calibration sheet is appended to this manual.

CHECK

TESTED BY : \_\_\_\_\_ DATE : \_\_\_\_\_

8. CONNECTION DIAGRAM

