



Order Number

Serial Number

Number in Batch

## PRODUCT/TEST MANUAL

**2HS522K10**

**30V DC HAND RESET MULTI-TRIP RELAY**

Issue Level	Date	Summary of changes
A	19/08/2004	Initial issue.
B	30/09/2004	Change operate time to <11.1ms at 30V DC including bounce.
C	20/10/2004	TfA Issue F
D	03/03/2005	TfA Issue G
E	26/05/2008	TfA Issue H
F	06/06/2008	Added check for overtravel of N/C contacts
G	12/09/2008	Added 2kV across open contact
H	04/08/2010	Added insulation resistance testing of all units

Due to RMS continuous product improvement policy this information is subject to change without notice.  
This document is uncontrolled and subject to copyright.

Author	Checked & Registered	.pdf file created	Released
ERL	DG	DG	

### 1. ASSOCIATED DRAWINGS

This Product Test Manual is used in conjunction with TfA 62182 Issue J 08/09/09.

### 2. INSULATION RESISTANCE CHECK

Check the insulation resistance at 500VDC for the following cases in Table 1. Note that the resistance shall be **no less than 100MΩ**.

**Table 1**

Terminals A	Terminals B
+1,-1,S1-S4	S5 – S8 & Earth
+1,-1, S1,S3,S5,S7	S2,S4,S6,S8 & Earth
+1,-1,S1,S2,S5,S6	S3,S4,S7,S8 & Earth
+1,-1	All & Earth
All	Earth
Across each open contact (note: S1-S4 are N/O and S5-S8 are N/C)	

### 3. HIGH VOLTAGE TESTING

Apply 2kV RMS 50Hz between terminals as in Table 1 below.

Apply three 5kV 1/50us pulses of each polarity between terminals as in Table 2 below.

**Table 2**

Terminals A	Terminals B
+1,-1,S1-S4	S5 – S8 & Earth
+1,-1,S2,S4,S6,S8	S1,S3,S5,S7 & Earth
+1,-1,S1,S2,S5,S6	S3,S4,S7,S8 & Earth
+1,-1,S7	S2 & Earth
All	Frame
Across each open contact	

### 4. TEST PROCEDURE

- Check that the coil resistance is 6.8 ohms (visual).
- Check that the resistance of the input is between 4 and 10 ohms.
- Wire all N/O contacts in series. Apply 30V DC and measure the operate time of the output contacts using the Matrix High speed relay Jig. Operate time is to be less than 11.1ms including bounce. Ensure flag operates and resets correctly with cover in place.
- Check operation of each normally closed contact, and check for sufficient overtravel.
- Check that the slugged relay contacts (RL2-1 and RL2-2) open in greater than 50ms at 30VDC.
- Check that the relay operates satisfactorily at 35V DC and 12V DC and that the armature is fully home. Ensure that no arcing occurs at the series contacts (RL2-1 and RL2-2) at 35V DC.

### 5. GENERAL & FUNCTIONAL

- Check external connections to Energy Australia's drawing 113553.
- Check the internal terminations at the base of the relay for tightness.



- c. Check adjustment of flag and flag reset mechanism
- d. Check that flags are labelled "**Main**" and "**Slave**" respectively, and that the face plate has a warning "**Relay is Non Auto unless Slave Flag has been reset**".
- e. Check that the operated burden is Zero
- f. Check that the relay has 1 spring washer, 3 nuts and two flat washers per stud.
- g. Check that the relay is electrically sound and mechanically robust as per Standard Inspection & Test Schedule 903-000-026.

**PASS**

TESTED BY: \_\_\_\_\_ DATE: \_\_\_\_\_