

Order Number

Serial Number

PRODUCTION TEST MANUAL

3Y31K8

REED REPEAT

Issue Level	Date	Summary of changes
A	25/02/13	Initial issue.

Due to RMS continuous product improvement policy this information is subject to change without notice.
This document is uncontrolled and subject to copyright.

Author	Checked	.PDF file created	Registered & Released
MVL	SG	SG	

1. BROAD DESCRIPTION OF RELAY

The 3Y31K8 is a dual element high speed relay with operate times less than 2 ms at the nominal voltage of 250 VDC

2. SPECIFICATIONS

DC Auxiliary Supply	250 VDC -30% + 10%
Supply Burden (At 250V DC)	Approx 2.7W
Speed of operation	Less than 2 ms @ 125 VDC.
Operating Contacts	Two normally open per element

3. ASSOCIATED DRAWINGS

182-031-108 Wiring Diagram
690-211-203 Circuit Diagram

4. TEST EQUIPMENT REQUIRED

DC Auxiliary Supply
Ammeter
HV Test Equipment
Doble Test Set
Jig294: 3Y31K4 Test Jig

5. HIGH VOLTAGE TESTING

- a) Apply 2kV RMS 50Hz between terminal Groups 1 and 2 in Table 1 for 1 minute.
- b) Apply 1kV RMS 50Hz between the terminals for one minute in Table 2

TABLE 1

GROUP 1	GROUP 2
1,12,7,6,9,4	5, 8,10,2,11,3
7,6,8,5,11,3	1,12,4, 9,10,2
1, 12, 8, 5,10,2	9, 4,11,3

TABLE 2

GROUP 1	GROUP 2
9, 10,8,11	4,2,5,3

6. TEST PROCEDURE

Before performing any of the following tests connect the coils of the relay to a 50 Hz supply for approximately 15 seconds. This flattens out any plating burrs that may cause sticking.

- a) Using a device for measuring operate time connect the auxiliary supply to relay 1
- b) For reed relay 1, measure the operate time at the minimum voltage specification (175V). This should be less than 3 ms. Record results for both contacts.
- c) Repeat b) for reed relay 2. **Note: If all results are less than 2ms, proceed to step e).**

	Relay 1	Relay 2
Nominal	3 ms	3ms
Actual	<input type="text"/>	<input type="text"/>

- d) Repeat b) and c) above but with voltage at nominal (250 VDC). This should be less than 2ms.

	Relay 1	Relay 2
Nominal	2 ms	2ms
Actual	<input type="text"/>	<input type="text"/>

- e) With each reed relay energised in turn, ensure that the operated burden (at 250VDC) is less than 2.7W - i.e. <10.8mA.

Check

- f) For reed relay 1, measure the drop out time at the maximum voltage specification (275V). This should be less than 3ms. Record results for both contacts.
- g) Repeat f) for reed relay 2.

	Relay 1	Relay 2
Nominal	3 ms	3ms
Actual	<input type="text"/>	<input type="text"/>

7. GENERAL & FUNCTIONAL

Check that the relay is electrically sound and mechanically robust as per Standard Inspection & Test Schedule 903-000-026.

PASS

TESTED BY: _____ DATE: _____

8. CONNECTION DIAGRAM

